



During months prone to snow, the structure or structures must be heated to 12° Celsius at the ridge to avoid the build up of snow.

During strong winds the structure or structures must be fully closed and sealed.

Transport and handling stillages and pallets used for the safe transportation of Losberger equipment will be required to be left on site during the event period, should this not be possible then additional transport charges will apply.

### Ground Penetration

All structures will be anchored to the ground using 30mm diameter steel ground pins driven to a depth of approximately 900mm - 1,200mm.

If services are present a detailed plan and surface identification marking the location must be supplied prior to commencement of erection.

Losberger UK Ltd is not responsible for any damage caused to underground services.

### Site Security

It is the responsibility of the hirer to ensure adequate protection against theft and vandalism from the time of arrival on site to the final removal from site of all Losberger equipment.

### Access

Clear unobstructed access to and from the chosen site for the assembly and dismantle must be made available for crew vehicles, articulated vehicles, forklift trucks, assembly and dismantle staff for all daylight hours during the agreed dates for assembly and dismantle including any subcontractors employed by Losberger UK Ltd.

Any restrictions may result in additional costs being charged to your final account.

### Assembly and Dismantle

For the assembly and dismantle we will require access onto the site with rough terrain forklift trucks, these will be used to transport the equipment from the delivery truck to the site where the assembly staff will assemble and dismantle the equipment.

The forklift truck will also be used to lift/hoist the main roof trusses into position, should the site be grass damage limitation measures may be necessary; the provision of this is the responsibility of the hirer.

The above quotation does not include any provision for the reinstatement of the site to its pre-hire state should any damage be incurred during the process of erection, dismantle or the event itself.